BOAT RAMP & CAR PARK UPGRADE KENNEDY DRIVE, TWEED HEADS PROPOSED WORKS



INDEX

DESCRIPTION	DWG NO.	ISSUE
INDEX & LOCALITY SKETCH	MNP23-01	1
NOTES	MNP23-02	1
EXISTING SERVICES AND DEMOLITION PLAN	MNP23-03	1
EXTENT OF WORKS PLAN	MNP23-04	1
STORMWATER LONGITUDINAL SECTION & TYPICAL SECTION	MNP23-05	1
LINEMARKING PLAN	MNP23-06	1
EROSION AND SEDIMENT CONTROL PLAN	MNP23-07	1
EROSION AND SEDIMENT CONTROL NOTES	MNP23-08	1

LEGEND

ISSUE 1, 2, 3, etc. = CONSTRUCTION ISSUE DRAWINGS

THE WORK WAS PERFORMED IN ACCORDANCE WITH THE DESIGN DRAWINGS.											
THE WORK PERFORMED HAS CHANGED FROM THE DESIGN DRAWINGS. REFER TO THE RED LINE CHANGES NOTED ON THE DRAWING SET.											
GANGER'S NAME	GANGER'S SIGNATURE	DATE									
SUPERVISOR'S NAME	SUPERVISOR'S SIGNATURE	DATE									

LOCALITY SKETCH





ISSUE A, B, C, etc. = PRELIMINARY APPROVALS / TENDER DRAWINGS (NOT FOR CONSTRUCTION)



ISSUED FOR CONSTRUCTION DATE^{18.10.17}

GENERAL

- 1. THIS NOTE AND THE FOLLOWING NOTES FORM AN INTEGRAL PART OF THIS DRAWING SET.
- 2. THESE DRAWINGS SHALL BE READ IN CONJUNCTION WITH THE RELEVANT TWEED SHIRE COUNCIL (TSC) DEVELOPMENT DESIGN SPECIFICATIONS AND STANDARD DRAWINGS.
- 3. ALL DIMENSIONS ARE IN METRES UNLESS SHOWN OTHERWISE.
- DIMENSIONS SHALL NOT BE SCALED FROM THE DRAWINGS.
- MATERIALS AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE SPECIFICATIONS. TOGETHER WITH THE REQUIREMENTS OF ALL APPLICABLE CODES OF PRACTICE, AUSTRALIAN STANDARDS AND STATUTORY AUTHORITIES.
- SURVEY DATA HAS BEEN COMPILED FROM FIELD PICK-UPS AND OFFICE RECORDS. THE PROJECT MANAGER SHOULD CONFIRM THAT SUFFICIENT DATA IS SHOWN TO ENABLE CONSTRUCTION WITHOUT DISTURBANCE TO FEATURES THAT ARE NOT SHOWN ON THE DRAWINGS
- 7. PRIOR TO ANY DEMOLITION, EXCAVATION OR CONSTRUCTION ON SITE, THE RELEVANT AUTHORITIES SHOULD BE CONTACTED FOR POSSIBLE LOCATION OF FURTHER UNDERGROUND SERVICES AND DETAILED LOCATION OF ALL SERVICES (DIAL BEFORE YOU DIG 1100)
- 8. THE TITLE BOUNDARIES SHOWN HEREON WERE NOT FIELD INVESTIGATED OR MARKED AT THE TIME OF SURVEY AND HAVE BEEN DETERMINED BY PLAN DIMENSIONS ONLY.
- THE ORIGIN OF CO-ORDINATES IS MGA.
- 10. THE DATUM FOR LEVELS IS AHD.

SITE WORKS

- 1. ALL SOILS CONTAINING ORGANIC MATTER (E.G. ROOTS, GRASS ETC.) MUST BE STRIPPED FROM THE CONSTRUCTION SITE PRIOR TO EARTHWORKS AND MUST NOT BE USED AS FILL MATERIAL.
- 2. CUT SLOPES MUST BE LIMITED TO 11/21 (HORIZONTAL:VERTICAL). THE SLOPE SHOULD THEN BE GRASSED OR PAVED TO PREVENT SCOUR AND EROSION DAMAGE

- THE CONSTRUCTOR SHALL CLEAN PAVEMENTS, LAWNS AND OTHER IMPROVED AREAS AND LEAVE THEM IN THE SAME ORDER AS THEY WERE AT THE COMMENCEMENT OF THE WORKS. THE CONSTRUCTOR SHALL RESTORE ANY FENCING REMOVED DURING CONSTRUCTION AND SHALL RESTORE LAWNS WITH TURF CUT AND SET ASIDE FROM THE ORIGINAL SURFACE AND WITH IMPORTED TURF FROM A SOURCE APPROVED BY THE CONSTRUCTION ENGINEER. (WSA 02 2002 PART 3, SECTION 25).
- 2. IMMEDIATELY AFTER BACKFILLING OF A TRENCH EXCAVATED THROUGH A PAVEMENT HAS BEEN COMPLETED, THE CONSTRUCTOR SHALL TEMPORARILY RESTORE THE PAVEMENT. WHERE THE TRENCH CROSSES BITUMEN OR CONCRETE PAVEMENT, THE SURFACE IS TO BE PROTECTED FROM DETERIORATION. A PRE-MIXED ASPHALTIC MATERIAL MAY BE USED FOR SUCH TEMPORARY RESTORATION. THE CONSTRUCTOR SHALL MAINTAIN THE TEMPORARY RESTORATION UNTIL FINAL RESTORATION IS CARRIED FINAL RESTORATION OF THE PAVEMENT SHALL BE CARRIED OUT TO RESTORE THE PAVEMENT AND ITS SUB-BASE TO NO LESS THAN THE ORIGINAL CONDITION. FINAL RESTORATION MAY INCLUDE, IF REQUIRED BY THE CONSTRUCTION ENGINEER, THE REMOVAL OF TEMPORARY RESTORATION.
- 3. IN OTHER THAN ROADWAYS, THE CONSTRUCTOR SHALL PLACE THE BACKFILL SUFFICIENTLY HIGH TO COMPENSATE FOR EXPECTED SETTLEMENT AND FURTHER BACKFILLING SHALL BE CARRIED OUT OR THE ORIGINAL BACKFILL TRIMMED AT THE END OF THE DEFECTS LIABILITY PERIOD IN ORDER THAT THE SURFACE OF THE COMPLETED TRENCH MAY THEN CONFORM WITH THE ADJACENT SURFACE.SURPLUS MATERIAL SHALL BE REMOVED AND DISPOSED OF TO AREAS ARRANGED BY THE CONSTRUCTOR. WHERE DRY WEATHER CONDITIONS HAVE PERSISTED AFTER THE ORIGINAL BACKFILLING. INCLUDING DURING THE DEFECTS LIABILITY PERIOD. THE CONSTRUCTOR SHALL TAKE ALL NECESSARY STEPS TO CONSOLIDATE THE TRENCH BEFORE REMOVING SURPLUS MATERIALS FROM THE SITE.
- 4. IN LOCATIONS WHERE. IN THE OPINION OF THE CONSTRUCTION ENGINEER. SURPLUS MATERIAL LEFT IN THE VICINITY OF THE TRENCH WOULD NOT BE OBJECTIONABLE, THE SURPLUS MATERIAL MAY BE DISPOSED BY SPREADING NEATLY IN THE VICINITY OF THE TRENCH TO THE SATISFACTION OF THE CONSTRUCTION ENGINEER IN SUCH A WAY AS TO AVOID FUTURE EROSION OF THE BACKFILL AND ADJACENT GROUND SURFACES. THE CONSTRUCTOR SHALL MAINTAIN THE BACKFILL AND ADJACENT GROUND UNTIL THE EXPIRY OF THE DEFECTS LIABILITY PERIOD.
- 5. WHERE, WITHIN PUBLIC OR PRIVATE PROPERTY, THE REASONABLE CONVENIENCE OF PERSONS WILL REQUIRE SUCH, THE CONSTRUCTION ENGINEER MAY ORDER THE CONSTRUCTOR TO LEVEL TRENCHES AT THE TIME OF BACKFILLING. THE CONSTRUCTOR SHALL MAKE GOOD ANY SUBSEQUENT SETTLEMENT, AS REQUIRED BY PLACING ADDITIONAL FILL.
- 6. THE CONSTRUCTOR SHALL IMMEDIATELY RESTORE ANY DAMAGED OR DISTURBED PRIVATE PROPERTY AND SERVICES.
- 7. SHOULD THE CONSTRUCTOR ELECT TO TUNNEL UNDER PAVING, KERB AND GUTTER OR OTHER IMPROVED SURFACES IN LIEU OF TRENCHING, BACKFILLING SHALL BE SO CARRIED OUT AS TO RESTORE FULL SUPPORT TO THOSE SURFACES. THE CONSTRUCTOR SHALL REMAIN RESPONSIBLE FOR THE REPAIR OF THE IMPROVED SURFACES, IF SUBSEQUENTLY DAMAGED DUE TO SUBSIDENCE OF THE BACKFILL, UNTIL THE END OF THE DEFECTS LIABILITY PERIOD.
- 8. THE CONSTRUCTOR SHALL PROVIDE NOTICE TO AFFECTED PROPERTY OWNERS OF ANY PENDING WORKS.

STORMWATER DRAINAGE NOTES

- DESIGN OF STORMWATER DRAINAGE HAS BEEN CARRIED OUT AS PER TWEED SHIRE COUNCIL DEVELOPMENT DESIGN SPECIFICATION D5 AND SUBDIVISION MANUAL SECTION A5.
- 2. STORMWATER DRAINAGE CONSTRUCTION SHALL BE CARRIED OUT IN ACCORDANCE THE TWEED SHIRE COUNCIL DEVELOPMENT CONSTRUCTION SPECIFICATIONS, IN PARTICULAR, C220 TO C233.
- STORMWATER DRAINAGE PIPES SHALL BE STEEL REINFORCED CONCRETE PIPES (CLASS SPECIFIED ON DRAWINGS) UNLESS OTHERWISE APPROVED.

EXISTING SERVICES

- EXISTING SERVICES SHOWN ON PLANS ARE AN INDICATION OF SERVICES FOUND AT THE TIME OF DESIGN INVESTIGATION.
- QUALITY OF INFORMATION ON EXISTING UNDERGROUND SERVICES SHOWN ON PLANS ARE CLASSIFIED USING AS5488-2013 WITH QUALITY LEVELS A. B. C. AND D:
- POSITIVE IDENTIFICATION OF A POINT POSITION IN THREE DIMENSIONS
- WITH HORIZONTAL AND VERTICAL TOLERANCE OF 50mm
- B LOCATION RELATIVE TO SUBSURFACE FEATURE LOCATION IN THREE
- DIMENSIONS. EG INTERPRETATION BETWEEN TWO QL-A POINTS
- VINTERPRETATION OF APPROXIMATE HORIZONTAL LOCATION USING EXISTING RECORDS AND SITE SURVEY OF VISIBLE SURFACE FEATURES. PROVIDES RELATIVE SPATIAL POSITIONING.
- COMPILED FROM ANY OR A COMBINATION OF: a.EXISTING RECORDS
 - **b.CURSORY SITE INSPECTION**
- c. ANECDOTAL EVIDENCE
- BY DEFAULT, IF THE DRAWINGS DO NOT INDICATE A QUALITY LEVEL 3. THEN THE INFORMATION SHALL BE ASSUMED TO BE AT QUALITY LEVEL Π
- THE CONSTRUCTOR SHALL BE RESPONSIBLE FOR THE LOCATION OF EXISTING SERVICES PRIOR TO COMMENCING WITH THE WORKS.
- THE CONSTRUCTOR SHALL BE RESPONSIBLE FOR THE REPLACEMENT OF 5. ANY EXISTING SERVICES DAMAGED DURING CONSTRUCTION WITH NEW SERVICES OF EQUIVALENT TYPE AND SPECIFICATIONS.
- WHEN CONSTRUCTING OR WORKING NEAR EXISTING PRESSURE MAINS IT SHOULD BE EXPECTED THAT THERE ARE CONCRETE THRUST BLOCKS LOCATED AT BENDS OR OTHER FITTINGS ON THE EXISTING MAIN. IT IS VERY IMPORTANT NOT TO DISTURB THE BEARING SOIL BEHIND THE THRUST BLOCK TO AVOID FAILURE OF THE EXISTING PRESSURE MAIN. IF EXCAVATION AROUND EXISTING THRUST BLOCKS CAN NOT BE AVOIDED THEN THE EXISTING PRESSURE MAIN SHALL BE TAKEN OFF LINE DURING THE EXCAVATION WORKS.

CONCRETE NOTES

- 1. ALL WORKMANSHIP AND MATERIALS SHALL BE IN ACCORDANCE WITH A.S.3600, CURRENT EDITION WITH AMENDMENTS
- 2. CONCRETE QUALITY (UNLESS OTHERWISE SHOWN) SHALL BE AS
 - FOLLOWS COURSE AGGREGATE - MAXIMUM SIZE 20mm
- CEMENT TYPE "A" PORTLAND CEMENT.
- CONCRETE SHALL HAVE THE FOLLOWING SLUMP DURING PLACEMENT - BEAMS ,SLABS AND FOOTINGS 80mm - COLUMNS AND WALLS 80mm
- 3. SLAB JOINTS SHALL BE PLACED AS FOLLOWS
- FOOTPATHS AS PER TWEED SHIRE COUNCIL STANDARD DRAWING NUMBER S.D.014
- SLABS AND WALLS REFER TO SLAB JOINTING PLAN WITHIN THIS DRAWING SET
- SLAB SAWN JOINTS SHALL BE CUT WITHIN 24 HOURS OF SLAB POURING IN A NEAT AND STRAIGHT CUT.
- 4. ALL SPLATTER TO SURROUNDING SURFACES SHALL BE CLEANED UP IMMEDIATELY
- COVER TO REINFORCEMENT SHALL BE OBTAINED BY THE USE OF 5 PLASTIC BAR CHAIRS WITH MAXIMUM SPACING OF 800mm IN ANY DIRECTION
- 6. ALL CONCRETE SHALL BE COMPACTED USING HIGH FREQUENCY VIBRATORS.
- 7. CURING OF CONCRETE SURFACES SHALL COMMENCE IMMEDIATELY AFTER SURFACES ARE FINISHED AND SHALL CONTINUE TO CURE FOR A MINIMUM OF 7 DAYS
- 8. SLABS WITH SPECIFIC ROUGH FINISHES SHALL BE KEPT FREE OF BLEED WATER AND FLOATED TO PREVENT THE FORMATION OF PLASTIC SHRINKAGE CRACKS
- 9. SLAB THICKNESSES AS SHOWN ON THE DRAWINGS DO NOT INCLUDE ANY FINISHES INCLUDING STAMPING DEPTHS.

'WORK AS EXECUTED' REPORTING

REQUIREMENTS

WORK AS EXECUTED INFORMATION MUST BE PROVIDED TO THE DESIGN UNIT BY THE CONSTRUCTION ENGINEER OR SITE FOREMAN AS A PART OF THIS WORK.

- 1. WHERE WORK IS CONSTRUCTED BY TSC STAFF REFER TO THE WATER UNIT'S 'WORK AS EXECUTED' PROCEDURE FOR WATER UNIT CAPITAL WORKS'.
- 2. WHERE WORK IS CONSTRUCTED BY CONTRACTORS REFER TO THE CONTRACT SPECIFICATIONS FOR 'WORK AS EXECUTED' REQUIREMENTS

	CONSTRUCTION				-	DES	IGN UNIT						o I		PROJECT	K
					-		OFFICES		TWEED	DESIGN ENGI	INEER	WA I	by	DATE 11.10.17		
						MURWIL	LUMBAH NSW 2484.			DESIGNED	N.O ⁴	19.07.17	/			IE:
										DRAWN	N.O ⁻	19.07.17 CC	OORDS ADOPTED	PM41250		
				40.40.47		PHONE	02 66702400		SHIKE GUUNGL	CHECKED	J.M.M.	19.07.17	EASTING	552145.608	1	
1		IN.O.	J.M.M.	18.10.17		FAX	02 66727513			HORIZONTAL	DATUM	MGA	NORTHING	6882057.637	1	
ISSUE	AMENDMENT DETAILS	DRAW	N CHECK	DATE	# USE FIGURED DIMENSIONS ONLY. DO NOT SCALE.	WEBSITE	www.tweed.nsw.gov	.au		VERTICAL D	MUTA	AHD	R.L.	1.864		
ACAD F	FILE No: G:\ AAA DESIGN PROJECTS\MNP\MNP23 Kennedy Drive Boat Ramp Carpa	rk Upgrade	Drawings\B	CONSTRUC	CTION DRAWINGS\MNP23 ISSUE FOR CONSTRUCTION.dwg										-	

1.

2.

3

4

5

6

8

4

ROAD PAVEMENT CONSTRUCTION INSPECTION AND TEST PLAN

THE ROAD PAVEMENT BOX SHALL BE EXCAVATED OR FILLED TO THE DEPTH AS SPECIFIED IN THE PAVEMENT DESIGN (REFER TO ROAD CROSS SECTION DRAWINGS) AND AS PER TWEED SHIRE COUNCIL DEVELOPMENT CONSTRUCTION SPECIFICATION C213 SUB SURFACE DRAINAGE SHALL BE CONSTRUCTED UNDER ALL KERBING AS SHOWN ON THE DRAWINGS AND SHALL BE IN ACCORDANCE THE TWEED SHIRE COUNCIL DEVELOPMENT CONSTRUCTION SPACIFICATION C230 WHERE JOINING INTO EXISTING ROADWAY CONSTRUCTION, REFER TO TIE IN DETAILS ON THE DRAWINGS FOR TREATMENT OF THE JOINING INTERFACE THE SUBGRADE SHALL BE PROOF ROLLED IN AN APPROVED MANOR AND ANY SOFT SPOTS IDENTIFIED SHALL BE EXCAVATED OUT AND REPLACED AS PER TWEED SHIRE COUNCIL DEVELOPMENT CONSTRUCTION SPECIFICATION C213 SUB BASE GRAVEL SHALL BE PLACED, SPREAD, WATERED AND COMPACTED TO TWEED SHIRE COUNCIL DEVELOPMENT CONSTRUCTION SPECIFICATION C242 KERBING (IF REQUIRED) SHALL BE CAST IN PLACE AFTER TESTING OF SUB BASE GRAVEL BASE COURSE GRAVEL SHALL BE PLACED, SPREAD, WATERED AND COMPACTED TO TWEED SHIRE COUNCIL DEVELOPMENT CONSTRUCTION SPECIFICATION C242 SEALING OF ROADWAY SHALL BE CARRIED OUT AFTER TESTING OF BASE COURSE GRAVEL

SET OUT INFORMATION

SET OUT INFORMATION FOR CONSTRUCTION IS PROVIDED TO THE CONSTRUCTION SURVEYOR IN DIGITAL FORM. SET OUT FOR ALL PIPEWORK IS CENTRE OF PIT (U.N.O.) SET OUT FOR ALL KERB AND GUTTER (INCLUDING DISH DRAIN) IS LIP OF KERB (REFER FIG 1 BELOW) SET OUT FOR ALL KERB ONLY (INCLUDING FLUSH EDGE STRIP) IS BITUMEN LEVEL AT FRONT FACE OF KERB (REFER FIG 1 BELOW) SET OUT FOR BITUMEN IS FINISHED SURFACE FINISHED SURFACE LEVEL SET OUT FOR STORMWATER DRAINAGE GULLY PITS IS AT THE LIP OF KERBING (REFER FIG 2 BELOW) FINISHED SURFACE LEVEL SET OUT FOR MANHOLES (SEWER AND STORMWATER), JUNCTION PITS, FIELD INLETS ETC. IS CENTRE OF LID / GRATE (REFER FIG 2 BELOW)





FIGURE 2









ACAD FILE No: G: AAA DESIGN PROJECTS/MNP/MNP23_Kennedy Drive Boat Ramp Carpark Upgrade/Drawings/B_CONSTRUCTION DRAWINGS/MNP23_ISSUE_FOR_CONSTRUCTION.dw

noo non dwy

			U)
INLET PIT D UCT			
0.6RATED I 050X1050 V-GRATE SURROUNI VED PROD VED PROD			
PROPOSED PIT SIZE: 1 RCLLA PIT CONRETE OR APPRO OR APPRO			
		,	۲L
			NG HEAW?
		```````````````````````````````````````	EXISTI
057			362
252 +2.			500 +0.
-0			0.138 -0
1 1			2.188 -0
ň			<u>،</u>
<u>10N</u> 50			
SAW CUT	NOTE	<u>S:</u>	
0.30 	1. DEPTH EXCEED EXISTING 2. SEAL J	OF NEW PAVEMENT DEPTH OF ADJACEN PAVEMENT BY 50mr OINT TYPES: AC TO /	TO T m (MIN.) AC -
	SAWCUT SHOWN ( PROVIDE	EXISTING AC WHERI DR AS AGREED ON S A CLEAN JOINT.	E ITE TO
ASE COURSE			
JOINT DETAIL A3 SCALE 1:50			
ENNEDY DRIVE BOAT RAMP CAR PARK UPGRADE		PROJECT NUMBER:	23
RMWATER LONGITUDINAL SECTION	1&	DRAWING NUMBER	ISSUE
TYPICAL SECTION		MNP23-05	1

 $\overline{(3/3)}$ 

 $\left( 2/3 \right)$ 





ENNEDY DRIVE BOAT RAMP CAR PARK UPGRADE	PROJECT NUMBER: MNP23
SION AND SEDIMENT CONTROL	DRAWING NUMBER ISSUE
PLAN	<b>MNP23-07</b> 1





#### **Construction Notes**

1. Install a 400mm minimum wide roll of turf on the footpath next to the kerb and at the same level as the top of the kerb

- 2. Lay 1.4 metre long turf strips normal to the kerb every 10 metres.
- 3. Rehabilitate disturbed soil behind the turf strip following the ESCP/SWMP.

**KERBSIDE TURF STRIP** 

#### EROSION & SEDIMENTATION CONTROL COMMENTARY

- MONITOR 7 DAY RAIN FORECAST TO DETERMINE TIMING 1. OF WORK.
- AVOID WORK IN WET WEATHER, ESPECIALLY WITHIN THE 2. ROAD SURFACE.
- LIMIT AREAS OF DISTURBANCE & MAINTAIN GRASSED 3. AREAS WHERE POSSIBLE. ENSURE GUTTERS, PATHWAYS & ROADS ARE SWEPT CLEAN PRIOR TO RAIN OR AT THE END OF SHIFT. HARD SURFACES CLEAN OF SOIL WILL REDUCE EROSION & SEDIMENTATION CONTROLS & THEREFORE TRIP HAZARDS TO PEDESTRIANS & ROAD HAZARDS ETC.
- ENSURE THAT TURF IS REPLACED AS SOON AS 4. POSSIBLE AFTER WORKS TO AID IN SOIL STABILISATION.
- REMOVE ESC MEASURES WHEN SITE IS CONSIDERED 5 STABILISED E.G. ESTABLISHED TURF ON EXCAVATED AREAS. REPLACE PAVEMENT ETC.
- ARRANGE REGULAR INSPECTIONS TO REVIEW & UPDATE 6. CONTROL MEASURES.

### EROSION AND SEDIMENT CONTROL PLANS

- MINIMISE EXTENT AND DURATION OF DISTURBANCE
- UNDISTURBED WHERE POSSIBLE.
- PREVIOUS STAGE)
- POSSIBLE)
- CONTROL STORMWATER FLOWS ONTO, THROUGH AND FROM THE SITE

- STRIPPING
- THAN 10 DAYS

SD 6-13

ARFAS

USE SEDIMENT CONTROL MEASURES TO PREVENT OFF-SITE DAMAGE THE INSTALLATION OF ALL EROSION AND SEDIMENT CONTROLS TO OCCUR IMMEDIATELY POST CLEARING AND

- STRIPPING

STABILISE DISTURBED AREAS QUICKLY

- POSSIBLE AFTER COMPLETION OF CONSTRUCTION WORKS.
- AFTER REINSTATEMENT.

MANAGEMENT PROGRAM.

INSPECT AND MAINTAIN CONTROL MEASURES ENSURE THE PROGRESSIVE AND CONTINUAL IMPLEMENTATION AND MAINTENANCE OF TEMPORARY EROSION

- AND SEDIMENT CONTROLS
- AND DISTURBED AREAS HAVE STABILISED.

ROADS CONSTRUCTION 2008

This sediment and erosion control plan contains Council's minimum requirements for environmental protection; however, it is still the principal contractor's responsibility to ensure that the works and mitigation strategies are performed in a manner that complies with all relevant environmental legislation, including any development approval requirements.

	PROVAL
۲	l. Cembrdge
ENVIRO	MENTAL SCIENTIST
	19.07.2017

	CONSTRUCTION					DESIGN UNIT							PROJECT NUMBER:	
	CONSTRUCTION											CAR PARK UPGRADE		23
	FOR CONSTRUCTION				SCALE: A1 SHEET 1:125, A3 SHEET 1:250   0 2.5 5 7.5 10 12.5r	TUMBULGUM ROAD,		DESIGN ENGI	NEER		DATE			-0
						MURWILLUMBAH NSW 2484.		DESIGNED	N.O 19.07.17 N.O 19.07.17	COORDS ADOPTED	PM41250		DRAWING NUMBER	ISSUE
1	ISSUE FOR CONSTRUCTION	N.O.	J.M.M.	18.10.17		PHONE 02 66702400	SHIRE COUNCIL	CHECKED	J.M.M. 19.07.17	EASTING	552145.608	NOTES		
ISSUE	AMENDMENT DETAILS	DRAWN	СНЕСК	DATE	# USE FIGURED DIMENSIONS ONLY. DO NOT SCALE	WEBSITE www.tweed.nsw.gov.au		VERTICAL D	ATUM MGA	NORTHING R.L.	6882057.637 1.864	-		1
ACAD FI	ACAD FILE No: G:_AAA DESIGN PROJECTS/MNP/MNP23_Kennedy Drive Boat Ramp Carpark Upgrade/Drawings/B_CONSTRUCTION DRAWINGS/MNP23_ISSUE_FOR_CONSTRUCTION.dwg													

PROGRESSIVE ERSED PLANS SHALL BE DEVELOPED AND IMPLEMENTED AS REQUIRED BY THE SITE SUPERVISOR BASED ON THIS PLAN AND FOLLOWING PRINCIPLES AND STANDARD SITE CONTROL MEASURES.

CONSTRUCTION WORKS TO BE MANAGED SUCH THAT AREAS OUTSIDE SCOPE OF WORKS REMAIN

MINIMISE EXTENT OF DISTURBANCE WITHIN CONSTRUCTION SITE AT ANY ONE TIME BY STAGING THE WORKS (EG. RIP EXISTING BITUMEN IN SECTIONS, MOVING ON TO NEW SECTIONS FOLLOWING COMPLETION OF

MINIMISE DISTURBANCE OF VEGETATION ALONG THE ROAD VERGE WITH SPECIAL EMPHASIS ON MANAGEMENT OF CONSTRUCTION ACTIVITIES ADJACENT TO TO WATERCOURSES (E.G. MAINTAIN GRASSY BUFFER WHERE

SEPARATE 'CLEAN' RUN-ON WATER FROM 'DIRTY' (E.G. TURBID) CONSTRUCTION AREA RUNOFF (MAINTAIN CLEAN WATER PASSAGE THROUGH CULVERT CROSSING THROUGHOUT CONSTRUCTION WORKS). CONSTRUCT PERMANENT DRAINAGE STRUCTURES EARLY IN THE PROJECT

USE EROSION CONTROL MEASURES TO PREVENT ON-SITE DAMAGE THE INSTALLATION OF ALL EROSION AND SEDIMENT CONTROLS TO OCCUR IMMEDIATELY POST CLEARING AND

SITE STOCKPILES OF SOIL MATERIAL IN LOW-HAZARD AREAS CLEAR OF WATERCOURSES, ADDITIONAL PROTECTION TO BE AFFORDED WITH TEMPORARY VEGETATION, DIVERSION BANKS AND SEDIMENT CONTROL MEASURES, IF REQUIRED. SEED STOCKPILES WITH ANNUAL GRASS IF THEY ARE TO BE STORED LONGER

CONSTRUCT A RANGE OF EROSION CONTROLS WITHIN THE VARIOUS ROAD SUB-CATCHMENTS TO COMPLEMENT AND INCREASE THE EFFECTIVENESS AND EFFICIENCY OF SEDIMENT CONTROLS IN THE LOWER

CONSTRUCT CONTROL MEASURES AS CLOSE TO THE POTENTIAL SOURCE OF SEDIMENT AS POSSIBLE. CONTROL THE DEPOSITION OF MUD AND SOIL MATERIAL ONTO LOCAL ROADS.

ALL REINSTATEMENT WORKS ADJACENT TO NEW CONSTRUCTION SHALL BE CARRIED OUT AS SOON AS ALL DISTURBED VERGES TO BE STABILISED BY REVEGETATING WITH APPROPRIATE SPECIES (E.G. ANNUAL

GRASS SEED SUCH AS ANNUAL RYEGRASSS OR JAPANESE MILLET, OR TURF) AS SOON AS PRACTICAL

ENSURE THE SUCCESS OF THE LATER REVEGETATION PROGRAM BY UTILISING A GOOD TOPSOIL

INITIATE A PROGRAM TO ENSURE REGULAR MAINTENANCE OF ALL EROSION AND SEDIMENT CONTROL MEASURES. SEDIMENT CLEANED FROM STRUCTURES (E.G. SCRAPE AWAY ACCUMULATED SEDIMENT UPSTREAM OF CHECK DAMS AND REPLACE/REPAIR AS NECESSARY) TO MAINTAIN FUNCTIONALITY. ARRANGE REGULAR INSPECTIONS BY AN ENVIRONMENTAL SCIENTIST TO REVIEW AND UPDATE CONTROL MEASURES. ADDITIONAL INSPECTIONS WILL BE CONDUCTED DURING AND/OR IMMEDIATELY FOLLOWING SIGNIFICANT RAINFALL EVENTS TO MONITOR THE FUNCTIONING OF CONTROLS. ALL EROSION AND SEDIMENT CONTROLS TO BE MAINTAINED IN PLACE UNTIL ALL WORKS ARE COMPLETED

EXTRACT FROM LANDCOM (2004). MANAGING URBAN STORMWATER: SOIL AND CONSTRUCTION. VOLUME 2D MAIN